12. Rates must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any rates quoted at so much percentage less or more than estimated rate will not be accepted.

Tender for constructing Married Men's quarters in Mysore Transport, Hebbal, Bangalore.

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
1	Earthwork excavation for foundation and filling in basement and carting the excavated earth to a distance not less than 50 yds. and refilling the excavated earth to the basement duly watering and tamping in layers of 6″ thick in all sides ..	C.yd.	..	44	
2	Burnt stone jelly concrete in lime mortar (jelly of 1″ to 1¼″ thick cubes) with the proportion of 1 part of lime to 2½ parts of sand and 4 parts of jelly for foundations laid in layers of 6″ thick with consolidation	C.ft.	..	294	
3	Size stone in clay for foundation the courses should not be less than 8″ high with bond stones at every 6′ apart with one line dressing at the faces and quoir dressing for basement	C.ft.	..	1,144	
4	Burnt brick in mud inserting bond stones	,,	..	2,534	
5	Burnt stone slabs 6″ thick, roughly dressed and fixed in mortar	S.ft.	..	222	
6	Burnt stone slabs 6″ thick, one line dressing on exposed faces and fixing	,,	..	80	
7	T. W. panelled doors with two shutters including iron fittings, etc.	,,	..	159	
8	T. W. windows with ¾″ iron bars panelled shutters and iron fittings, etc., complete	,,	..	71	
9	Roofing with R.C.C. 6″ thick as per standard specification and calculation	Sqr.	..	6·69	
10	Providing cement concrete chajja over doors and windows in front 3′ projecting 3″ to 2½″ thick ..	S.ft.	..	162	
11	R.C. ventilators including fixing charges	,,	..	24	
12	R.S. girder 9″×3″ including fixing charges, hoisting, carting, etc.	Cwts.	..	5	
13	Lime plastering walls	Sqr.	..	40·40	
14	White washing 2 coats as per plastering	,,	..	40·40	
15	Flooring with cement concrete 1½″ thick over 3″ lime concrete with red coloured cement plastering and smooth finish	Sqr.	..	5·71	
16	Cement drain with cement plastering on slab foundation.	R.ft.	..	47	
17	Painting to doors and windows with 2 coats of Lac Factory Green paint	Sqr.	..	40·03	
18	Providing and fixing R.C.C. slabs for partition walls, with coping and fixing	S.ft.	..	334	
19	Constructing over in kitchen with burnt brick in mud, and plastering with cover slab and chimney ..	No.	..	2	
20	Cement pointing to basement	Sqr.	..	3·70	
21	Constructing parapet wall of 1½′ height including and plastering all round and; etc., complete	R.ft.	..	91¼	
22	Providing mortar band alround	,,	..	91¼	
23	Providing mortar and pestle stones	L. S.	..	..	
24	Providing sinks and ovens in kitchen and bath as per instruction	,,	..	..	
25	Providing teakwood shelf planks with pegs ..		..	..	

M. K. RAJAM IYENGAR,
Executive Engineer.

MANDYA DIVISION.

Notification dated 30th March 1940.

1. Sealed tenders will be received at the Office of the Executive Engineer, Mandya Division, up to 12 NOON on 22nd April 1940, for restoring Thenginaghatta minor tank, Reg. No. 1137, Krishnarajpet Taluk.

2. Tenders in the prescribed form obtainable from the Office of the Executive Engineer, Mandya Division, on payment of annas four per form should be addressed to the Executive Engineer, Mandya Division, in a sealed cover and superscribed as "Tender for restoring Thenginaghatta minor tank, Reg No. 1137, Krishnarajpet Taluk." The name of the tenderer should also be superscribed on the top of the cover.

3. Each tender must be accompanied by a Treasury chellan for the deposit of Rs. 200 (in words Rupees two hundred) paid to the Treasury to the credit of "17 (a) Deposits of Executive Engineer, Mandya Division, Mandya." The earnest money of the successful tenderer will be retained as security deposit for the due fulfilment of the contract. Such a deposit in cash will not carry any interest.

4. The tenders will be opened in the presence of such tenderers who wish to be present on 23rd April 1940 at Mandya Division. The final acceptance of the tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Executive Engineer's office in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute an agreement in the Departmental Schedule Contract Form, for the due fulfilment of the contract, and for the execution of all items of work in accordance with the Bombay specifications (1931). The earnest money tendered will be treated as security deposit for the due fulfilment of the contract.

6. Failure to comply with the condition 5 above or to agree to carry out the work in accordance with the specifications and agreements in force will entail forfeiture of the earnest money.

7. The earnest money of rejected tenders will be returned on production of duplicate Treasury chellans originally granted, by the Treasury Officer for having remitted earnest money.

8. Copies of contract documents, schedules and drawings may be seen at any time at the Executive Engineer's Office, Mandya, on all working days, between 11 A.M. and 5 P.M.

9. Specific rates should be given for each item in the schedule accompanying the tender and the rates should be in rupees, annas and pies and expressed in words and figures. Tenders offering a percentage reduction on the estimate amount will be rejected.

10. Any rates or lumsump amounts for the items not called for, if tendered by the tenderer, will not be taken notice of. The rates for such items may be entered in a separate schedule with date and reasons for the same.

11. No alterations which are made by the tenderers in the tender form in the nomenclature of the items of work will be recognised and if corrections are made, the tenders are liable to rejection.

12. There should be no alterations or erasures in the tenders in the rates of items and any corrections made in the rates should be attested to and the number of corrections, if any, in each page noted at the foot of the same by the tenderer.

13. No reference should be made to the Public Works Department schedule of rates.

14. In the event of the tender being submitted by a firm, it must be signed separately and severally by each member thereof or in the event of absence of any partner, it must be signed on his behalf by a person holding power-of-attorney authorising him to do so.

15. When once the rates tendered have been accepted, they will not be revised under any circumstances. In regard to items of work not tendered, the rates for the same will be calculated by the Executive Engineer on the basis of current rates for materials and labour with a contractor's profit of 5 per cent as may be approved by the Superintending Engineer. This shall be final and legally binding on the tenderer.

16. The quantities given in the Schedule are only approximate and the drawings shown to the contractor are only tentative and are liable to alterations, omissions, deductions or additions, at the discretion of the Executive Engineer or his representative. The tendered rates will hold good for any quantity, whether higher or lower than those given in the enclosed schedule.

17. The work should be completed and handed over in a tidy condition to the Public Works Department by the end of June 1940, failing which the Executive Engineer may, at his discretion, levy a penalty of Rs. 5 (five) per day, which will ordinarily be calculated at 12 per cent per annum on the total outlay as liquidated damages for non-fulfilment of contract, and will be recovered from the contractor's outstandings for the period exceeded by him beyond the time fixed and until the work is completed and handed over.

18. In all matters of disputes of any kind not specially provided for in the agreement or of rates, penalties, meaurements, quality of work, etc., the decision of the Chief or the Superintending Engineer shall be final and legally binding.

19. No claim for damages for delays caused by officers of the department in the execution of the work will be considered, whatever may be the reasons for such delays. Contractors should bear this in mind when tendering for the work. Extension of time due to delays caused by the departmental officers will, however, be considered on the merits of each case.

20. The contract should not be sublet.

21. All materials, tools and plant and machinery that will be supplied by the Executive Engineer in the interest of the work shall be accepted by the tenderer at the rates fixed by the Executive Engineer. The tenderer will pay the hire on tools and plant and machinery as per rules from the

date of taking over of such machinery, tools and plant from the Stores to the date of return thereto, the dates considered being the dates of acknowledgments of the vouchers in each transaction.

22. The contractor should arrange for the payment of royalty and tolls.

Note.—(*a*) The contractor should at his own cost—

(1) Provide rods, stakes, ropes and labour required in setting out the works.
(2) Provide all necessary scaffolding, centering labour and appliances for hoisting.
(3) Provide mortar mills and sheds, to keep materials under cover and also for workmen.
(4) Arrange for protecting work during inclement weather.
(5) Supply requisite temporary lights, water cisterns, water pumps and hoses, sieves, pails, shoring, strutting and other requisite protective appliances during the progress of the work.
(6) Supply all water required for work and workmen and shall provide temporary latrines and drains.
(7) Clean away all dirt, rubbish, superfluous materials and debris as they accumulate.
(8) Provide arrangements for pumping and baling of water from excavations and foundations, wherever and whenever necessary with his own pumping apparatus including necessary leading drains, slump pits, etc.
(9) Afford facilities to any other parties employed upon the work by the P. W. D. so that their work may proceed during the progress of the contract, and give such persons the use of ordinary scaffolding and ladders.
(10) The contractor is responsible for all accidents to workmen, etc., on the work, and he must take precaution against all risk of accidents and, if necessary provide for the same by insurance at the proper time.

Note.—(*b*) It is the business of the contractor to make his own arrangements for quarries and supplies of materials.

Restoration of Thenginaghatta Minor Tank Register No. 1137, Krishnarajpet Taluk.

No.	Particulars	Per	Quantity	Rate	Cost
				Rs. a. p.	Rs.
	I. BUND R. L. 51·00.				
1	Clearing jungle with roots	Grade	20	1 8 0	
2	Cutting grips and trenches	C.yd.	362	0 1 6	
3	Earth work to bund with watering and consolidation.	C.yd.	6,241	0 4 6	
4	Earth work to bund with consolidation (as per above deductions)	„	465	0 1 0	
5	Gravelling the top of bund	„	91	0 8 0	
6	Turfing the slopes	Sqr.	608·44	0 9 0	
7	Providing and fixing grade stones in cement concrete (1 : 3 : 6)	Each	23	2 8 0	
8	Providing and fixing Index stones	„	23	0 8 0	
9	Do B. M. stones, complete	„	2	3 0 0	
10	Register No. stone, complete	„	1	5 0 0	
11	Gauge stones	„	1	12 0 0	
	II. SLUICE R. L. 49·00.				
1	Earthwork cutting open the bund and refilling the same with consolidation	C.yd.	41	0 5 0	
2	Size stone in cement mortar 1 : 6	C.ft.	150	0 6 0	
2(*a*)	Burnt brick in cement mortar (alternatively)	..	..	..	
3	Cement pointing, rates per sq. yd. to be quoted	..	..	..	
3(*a*)	Cement plastering	..	..	..	
4	Supplying and fixing C. S. pipes 6" dia. including jointing	R.ft.	24	3 0 0	
5	Rough stone work new	C.yd.	11	1 8 0	
(*a*)	Removing and resetting old stone work, rate per c.yd. to be quoted	..	..	..	
6	Providing and fixing jelly wood plug	Each	1	4 0 0	
	III. WASTE WEIR LEFT 91 FEET LONG R.L. 51·00.				
1	Earthwork excavation and using the same to the bund including watering and tamping, complete	C.yd.	465	0 4 0	

No.	Particulars	Per	Quantity	Rate	Cost
				Rs. a. p.	Rs.
2	Cement concrete 1 : 5 : 10	C.ft.	205	0 5 0	
3	Size stone in cement mortar 1 : 6	C.ft.	519	0 6 0	
4	Cement mortar pointing. Rate per square to be quoted				
5	Rough stone work new apron including jelly wedging..	C.yd.	32	1 8 0	

B. S. NARASINGA RAO,
Executive Engineer.

MISCELLANEOUS DEPARTMENTS.

OFFICE OF THE PRESIDENT, SRI NARASIMHARAJA HOSTEL, BANGALORE.

Tender Notice No. 731, dated 1st April 1940.

Sealed Tenders together with samples will be received by the Warden, Sri Narasimharaja Hostel, Bangalore, for the supply of provisions, milk and curds and stationery required for the hostel for 1940-41 on any day between the 10th and 15th of April 1940, during office hours, *viz.*, 8 A.M. to 11 A.M.

The conditions of tender and the approximate quantity and variety of provisions, etc., required are published in the *Mysore Gazette*, dated 22nd February 1940.

M. S. RAJAGOPAL RAU,
President.

MYSORE SERUM INSTITUTE, HEBBAL, BANGALORE.

Abstract Tender Notification dated 29th March 1940 for the Supply of He-buffaloes.

The attention of the public is invited to the detailed tender notice dated 16th March 1940, calling for sealed tenders for the supply of he-buffaloes to the Serum Institute, during the year 1940-41, published on pages 667 and 668, Part VI of the *Mysore Gazette*, dated 28th March 1940.

The last date for the receipt of the tenders in the Office of the Superintendent, Mysore Serum Institute, Hebbal, Bangalore, is 31st May 1940 up to 3 P.M.

Abstract Tender Notification dated 29th March 1940 for the supply of He-goats and Sheep.

The attention of the public is invited to the detailed tender notice dated 16th March 1940, calling for sealed tenders for the supply of he-goats and sheep to the Serum Institute during the year 1940-41, published on pages 670 and 671, Part VI of the *Mysore Gazette*, dated 28th March 1940.

The last date for the receipt of the tenders in the Office of the Superintendent, Mysore Serum Institute, Hebbal, Bangalore, is 31st May 1940 up to 3 P.M.

Abstract Tender Notification dated 29th March 1940 for the supply of buffalo, bull, calves and bull calves.

The attention of the public is invited to the detailed tender notice dated 16th March 1940, calling for sealed tenders for the supply of buffalo bull calves and bull calves to the Serum Institute, during the year 1940-41, published on pages 669 and 670, Part VI of the *Mysore Gazette*, dated 28th March 1940.

The last date for the receipt of the tenders in the Office of the Superintendent, Mysore Serum Institute, Hebbal, Bangalore, is 31st May 1940 up to 3 P.M.